



NOTES:

1. SEE 5-01 FOR STRUCTURAL GENERAL NOTES.
2. PROVIDE ARCH FOR ADDITIONAL INFORMATION AND DIMENSIONS, INCLUDING SLOPES AND SLAB DEPRESSIONS.
3. Fx INDICATES COLUMN FOOTING. SEE 1/5-3-01. T/Ft/G = 1'-4" UNO, BASED ON T/S/LAB REFERENCE ELEVATION. 0'-0" (CORRESPONDS TO 0'-0" FINISH FLOOR).
4. BpX INDICATES COLUMN BASE PLATE. SEE 3-5-3-02.
5. ———— INDICATES STEP IN FOOTING. SEE 1/5-3-02.
6. W/E2 INDICATES JOINT ON GRADE. PROVIDE JOINT WITH W/WF 6x6 W/2.1xw/2.1 ON VAPOR BARRIER AND 4" GRANULAR BASE, UNLESS NOTED OTHERWISE.
7. C.J. INDICATES SLAB CONTROL JOINT. SEE 1/5-3-02 AND GENERAL NOTES FOR ADDITIONAL INFORMATION.
8. PROVIDE ISOLATION JOINT AT COLUMN. SEE 2/5-3-02 AND 3/5-3-02.
9. PROVIDE REINFORCEMENT AT RE-ENTRANT CORNERS. SEE 1/5-3-01.
10. ———— INDICATES BRACKED FRAME. SEE SHEET 5-5-1.1.
11. ———— INDICATES SLAB DEPRESSION. SEE 5-5-1.1.
12. INDICATES 12" MASONRY WALL REINFORCED W/ #5@24" OC EACH FACE. SEE DETAIL 2/5-4-01.
13. INDICATES 8" MASONRY WALL REINFORCED W/ #5@32" OC SEE DETAIL 2/5-4-01.
14. PROVIDE ADDITIONAL REINFORCEMENT AT JAMES' CORNERS, ETC. OF MASONRY WALLS PER 1/5-4-01. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF ALL UTILITY AND PLUMBING LINES. SEE 7/5-3-02.
15. PROVIDE THICKENED SLAB AT ALL MASONRY PARTITION WALLS. SEE 1/5-3-01. COORDINATE LOCATION OF MASONRY PARTITION WALLS WITH ARCH.
16. S (S) INDICATES MASONRY WALL REINFORCEMENT. SEE 1/5-4-01 & 3/5-4-01.
17. PROVIDES CONCRETE REDESKTOP REINFORCEMENT.
18. PROVIDE 5/8" RODS FOR TYPICAL RE-ENTRANT BAR REINFORCEMENT AT CMU WALLS.



COVINGTON, GA 30014

Drawn By BS & SRC	Checked By HJ
Date 07/02/2026	Job No. 25033

S-1.01

RELEASED FOR CONSTRUCTION