

TOILET ACCESSORY SCHEDULE								
TAG NO.	DESCRIPTION	MANUFACTURER	MODEL	FURNISHED BY		INSTALLED BY		COMMENTS
				CONTRACTOR	OWNER	CONTRACTOR	OWNER	
	<varies>	<varies>	<varies>					<varies>
TA-A-01	1-1/2" DIA. 36 x 42 ADA GRAB BARS	BOBRICK	B-6806x36; B-6806x42	X		X		
TA-B-01	WALL MOUNTED SOAP DISPENSER	BOBRICK	B-4069	X		X		
TA-C-01	TOWEL DISPENSER/WASTE RECEPTACLE - RECESSED	BOBRICK	B-369	X		X		
TA-D-01	TOILET TISSUE DISPENSER	BOBRICK	B-3588					
TA-E-01	AVERY MIRROR - GLOSSY BURGUNDY	MDC MIRRORS	MHE51211BU	X		X		CONTACT JAMIE WALKER, JWalker@mdcwall.com, 470-862-8332
TA-F-01	MOP AND BROOM HOLDER; 36"	BOBRICK	B-223x36	X		X		
***TOILET ACCESSORIES HAVE NOT BEEN DISCUSSED W/ OWNER.			307 X 60	X		X		PROVIDE SHOWER CURTAIN RINGS AS REQUIRED

MILLWORK GENERAL NOTES

1. REFER TO INTERIOR ELEVATIONS, WHICH IDENTIFY THE ROOM AND WALL (NORTH, SOUTH, EAST OR WEST) ON WHICH THE CABINETRY IS LOCATED. COORDINATE ALSO WITH FLOOR PLANS.
2. SPECIALIZED CABINET SECTIONS ONLY ARE KEYED OR NOTED ON CABINET ELEVATIONS. OTHER CABINET SECTIONS ILLUSTRATE TYPICAL CONSTRUCTION & NOT EVERY DOOR AND/OR DRAWER VARIATION IS SHOWN.
3. ALL WORKSURFACES & COUNTERTOPS ARE PL-2 U.N.O.
4. PROVIDE FINISHED END PANELS AND/OR END RETURNS AT OPEN ENDED CABINETRY (INCLUDING KNEE SPACES).
5. PROVIDE P-LAM CLAD TRIM AND FILLER PANELS WHERE EQUIPMENT IS LOCATED WITHIN CABINET UNITS.
6. GLASS PANELS ARE 1/4" CLEAR TEMPERED GLAZING U.N.O.
7. PROVIDE SIDE SPLASHES WHERE COUNTERTOPS ABUT WALLS AT SIDES - U.N.O.
8. PROVIDE COUNTERTOP BRACE SUPPORTS AT 48" O.C. MAX. @ KNEE SPACES & LAVATORY COUNTERTOPS, U.N.O.
9. PROVIDE 3" DIA. GROMMETS AT BACK OF COUNTERTOPS EXACT LOCATION TO BE COORDINATED WITH THE OWNER IN THE FIELD AT THE TIME OF INSTALLATION.
10. PROVIDE BLOCKING WITHIN PARTITION FOR ALL CABINETRY ATTACHED TO WALLS. SEE DETAILS FOR ATTACHMENT DETAILS.
11. PROVIDE ALL STRAIGHT TRIM COUNTERTOPS THAT HAVE SINKS, WITH SEPARATE BACKSPLASH TO COUNTERTOP.
12. FILE DRAWERS ARE NOTED ON ELEVATIONS. PROVIDE MINIMUM INSIDE CLEAR DIMENSIONS OF 13.5" WIDE BY 10.5" HIGH BY 20.5" DEEP.
13. CABINET UNIT DEPTH IS AS SHOWN ON SECTION. U.N.O. IN ELEVATION(S).
14. FOR FIELD APPLIED MIRRORS, EXTEND MIRRORS FROM THE TOP OF COUNTERTOP SPLASH TO 6'-0" A.F.F., U.N.O.
15. PROVIDE BOTTOM CLOSURE FOR FILLER PANELS AT TOE SPACES AND AT BOTTOM OF UPPER WALL CABINETS TO CLOSE OFF AND SEAL TIGHT ALL CONCEALED OPENINGS.
16. ALL MILLWORK/CASEWORK TO BE PL-1 U.N.O.

CABINET HARDWARE:

DOOR HINGES TO BE BLUM T1T5880 CHROMED, CONCEALED, SELF-CLOSING.
DRAWER SLIDES TO BE HEAVY DUTY ACCURIDE HAFELE #4034.
DISCREETLY LOCATED TO BE MCKEETTY DRASS STAINLESS STEEL OR APPROVED EQUALS
MILLWORK REVEALS: PITTCO, VENEER CABINET, VP775-3838

ALL RECEPTION/WAITING MILLWORK TO BE PREMIUM GRADE

ALL EXAM ROOM MILLWORK AND P-LAM CASEWORK TO PER A/I STANDARDS.

ALL CABINET/FILES TO BE LOCKABLE

INTERIOR ELEVATION NOTES

1. GENERAL CONTRACTOR TO COORDINATE EQUIPMENT OUTLINED IN "EQUIPMENT LEGEND" WITH OWNER & OWNER'S MEDICAL EQUIPMENT REPRESENTATIVE. THIS INCLUDES VERTICAL AND HORIZONTAL MOUNTING HEIGHTS OF ALL DEVICES, COORDINATION WITH ARCHITECTURAL, MECHANICAL, ELECTRICAL & PLUMBING. THE ARCHITECT SHALL RECEIVE SHOP DRAWINGS SHOWING FINALIZED SELECTION OF EQUIPMENT AND SPECIFICA MODEL NUMBERS REVIEWED BY DESIGN TEAM/ENGINEERS PRIOR TO PROCEEDING WITH SCOPE OF WORK.
2. ELECTRICAL OUTLETS ARE ONLY SHOWN FOR COORDINATION WITH EQUIPMENT. SEE ELECTRICAL DRAWINGS FOR MORE INFORMATION.
3. LOW VOLTAGE BY OWNER'S REPRESENTATIVE.
4. FURNITURE OUTLETS TO BE PROVIDED BY OWNER U.N.O. GENERAL CONTRACTOR TO COORDINATE WITH OWNER ON DELIVERY SCHEDULE.



HIGHWAY 36
COVINGTON, GA 30014

RELEASED FOR CONSTRUCTION

