Room Schedule					
Number	Name	Wall Finish	Floor Finish	Base Finish	Ceiling Finish
1	Fellowship Area	5/8" Gypsum, Painted: TBD	LVT Floor Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD
2	Room	5/8" Gypsum, Painted: TBD	24" Sq. Carpet Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD
3	Room	5/8" Gypsum, Painted: TBD	24" Sq. Carpet Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD
4	Room	5/8" Gypsum, Painted: TBD	24" Sq. Carpet Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD
5	Room	5/8" Gypsum, Painted: TBD	24" Sq. Carpet Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD
6	Mechanical Rm	5/8" Gypsum, Painted: TBD	LVT Floor Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD
7	Closet	5/8" Gypsum, Painted: TBD	LVT Floor Tile. Style: TBD Color: TBD	Vinyl Cove Base. Color: TBD	24" Lay-In Ceiling Tile w/ Suspended Grid System. Specs: TBD

Door Schedule						
Mark	Count	Description	Width	Height	Finish	Hand
100	1	Store Front Type Double Door	6' - 0"	7' - 0"	3070 Narrow Style Store Front Door w/ 10" Bottom Rail. Clear Anodized aluminum door w/ safety glass, deadbolt-S. Parker #82162IC keyed-exit & thumbturn int. side, 1" round push bar/pull handle. Saddle Type aluminum threshold, 1 1/2 pair heavy duty hinges w/ non-removable pins. LCN 4040 Series door closure, weatherstripping & door sweep. Uo=0.28 SHGC = 0.25	RH & LH
101	1	Solid Wood Double Door	6' - 0"	7' - 0"	Painted to match (B.S.), Half Glass, Push Plates and Pull Handles, Heavy Duty Hinges	RH & LH
102	1	Insulated Metal Double Door	5' - 0"	7' - 0"	Painted to match (B.S.), Passasge Lever Handles, Heavy Duty Hinges	RH & LH
103	1	Insulated Metal Double Door	5' - 0"	7' - 0"	Painted to match (B.S.), Passasge Lever Handles, Heavy Duty Hinges	RH & LH
104	2	Solid Wood Door	3' - 0"	7' - 0"	Painted to match (B.S.), Half Glass, Passasge Lever Handles, Heavy Duty Hinges	RH
105	2	Solid Wood Door	3' - 0"	7' - 0"	Painted to match (B.S.), Half Glass, Passasge Lever Handles, Heavy Duty Hinges	LH
107	1	Solid Wood Door	3' - 0"	7' - 0"		

No.	Description	Date

PROFESSIONAL SEAL

CLIENT

Grace Baptist Church

PROJECT NAME

Building Addition

SHEET TITLE

Finish Schedules

PROJECT NUMBER

ADDRESS

4020 Hwy. 81
McDonough GA

DATE 03/19/2025

PROFESSIONAL IN CHARGE

PROJECT MANAGER

DRAWN BY TD

QUALITY CONTROL -

01-A4

Page 4 Of 9

Scale

4/8/2025 1:41:21 PM