

MECHANICAL DEMOLITION FLOOR PLAN
1/8" = 1'-0"


MECHANICAL NOTES: (THIS SHEET ONLY)

1. GENERAL: ALL ELECTRICAL POWER WORK, INCLUDING DISCONNECTING EXISTING UNITS AND REMOVAL OF ELECTRICAL DEVICES, CONDUIT, SMR AND WIRING SHALL BE DONE BY THE ELECTRICAL CONTRACTOR.
2. GENERAL: CONTRACTOR SHALL PROVIDE WEATHER PROTECTION FOR ALL BUILDING OPENINGS RESULTING FROM MECHANICAL EQUIPMENT REMOVAL.
3. REMOVE EXISTING GAS FIRED ROOFTOP AIR CONDITIONING UNIT AND ROOF CURB/CURB ADAPTER. REMOVE SUPPLY AND RETURN DUCT RISING THRU CURB TO UNIT. SEE ARCHITECTURAL FOR PATCHING OF ROOF DECK.
4. REMOVE EXISTING ROOF MOUNTED EXHAUST FAN AND ROOF CURB. SEE ARCHITECTURAL FOR PATCHING OF ROOF DECK.
5. REMOVE EXISTING WALL MOUNTED LOW VOLTAGE THERMOSTAT.
6. REMOVE EXISTING WALL SWITCHES SERVING EXHAUST FANS AND INTAKE LOUVERS.
7. REMOVE EXISTING WALL MOUNTED PROPELLER EXHAUST FAN AND BACKRAFT SHUTTER. BRICK/BLOCK INFILL OF OPENING TO BE PROVIDED BY ARCHITECTURAL.
8. REMOVE EXISTING ANGLE IRON FRAME AND EXPANDED METAL SCREEN AND WALL ANCHORS. PATCH BRICK FOLLOWING ANCHOR REMOVAL.
9. REMOVE EXISTING MOTORIZED INTAKE DAMPER REMOVE EXISTING INTERIOR ANGLE IRON FRAME AND EXPANDED METAL SCREEN. REMOVE EXTERIOR EXPANDED METAL SCREEN. BRICK/BLOCK INFILL OF OPENING TO BE PROVIDED BY ARCHITECTURAL.
10. REMOVE ALL EXISTING SUPPLY DUCT, SURFACE MOUNTED SIDEWALL GRILLES, AND DUCT SUPPORTS.
11. REMOVE EXISTING BRANCH DUCT AND CEILING SUPPLY GRILLE.
12. REMOVE EXISTING RETURN DUCT AND RETURN GRILLES.
13. REMOVE EXISTING COMMERCIAL DRYER FLUE AND ROOF FLASHING AND FLUE CAP. SEE ARCHITECTURAL FOR PATCHING OF ROOF DECK.
14. REMOVE EXISTING CAPPED ROOF FLASHING AND ANY ABANDONED DUCT. SEE ARCHITECTURAL FOR PATCHING OF ROOF DECK.



HCS - SRO Offices - Warhawk Fieldhouse
Modifications
47 LEMON STREET MCDONOUGH, GA 30253

BID SET



CLIENT		
HENRY COUNTY SCHOOLS		
DATE	PROJECT NUMBER	
06 / 18 / 2026	250306	
DRAWING HISTORY		
No.	Description	Date
CHECKED BY: JDR		
DRAWN BY: JDR		

MECHANICAL
DEMOLITION FLOOR
PLAN

MD-101