



1. PROVIDE VARIABLE AIR VOLUME (VAV) AS SCHEDULED. PROVIDE ALL ASSOCIATED SUPPORTS AND ANCILLARY DEVICES AS REQUIRED FOR A COMPLETE AND OPERABLE SYSTEM. REFER TO DRAWING M202 FOR ASSOCIATED DETAIL AND DRAWING M301 FOR SCHEDULED CAPACITY.
2. PROVIDE DUCTWORK AS SHOWN IN ITS ENTIRETY. PROVIDE ALL REQUIRED SUPPORTS, INSULATION, AND ANCILLARY DEVICES AS REQUIRED FOR A COMPLETE AND OPERABLE SYSTEM.
3. PROVIDE AIR TERMINAL DEVICES AS INDICATED ON PLAN. REFER TO M200 DWGS FOR ASSOCIATED DETAILS AND M300 DWG FOR SCHEDULED CAPACITIES
4. PROVIDE DUCTWORK DROP FROM EXHAUST FAN (EF) ABOVE. PROVIDE ALL REQUIRED TRANSITIONS FROM EF TO PLAN INDICATED DIMENSIONS. PROVIDE INSULATED MOTORIZED DAMPER AT THE BUILDING ENVELOPE
5. PROVIDE DUCTWORK DROP FROM ROOF TOP UNIT (RTU) ABOVE. PROVIDE ALL REQUIRED TRANSITIONS FROM RTU TO PLAN INDICATED DIMENSIONS. PROVIDE INSULATED MOTORIZED DAMPER AT THE BUILDING ENVELOPE



LINE IS 2 INCHES
AT FULL SIZE

APPROVED: RFJ

616202

CLIENT PROJECT NUMBER

M102