1 SECOND FLOOR LIGHTING PLAN - NEW WORK

SCALE: 1/8" = 1'-0"

GENERAL NOTES:

A. ALL EMERGENCY LIGHTING WILL BE WIRED TO BE SWITCHED ON/OFF WITH THE ROOM LIGHT SWITCH.

CONSTRUCTION NOTES:

1. PROVIDE (1) WALL MOUNTED OCCUPANCY SENSOR LIGHT SWITCH WITH DIMMING CAPABILITIES AT THIS LOCATION.
2. CIRCUIT NEW LUMINAIRES TO EXISTING LIGHT SWITCH BRANCH CIRCUIT IN THIS CORRIDOR LOCATION.
3. CIRCUIT NEW LIGHT SWITCHES TO EXISTING LUMINAIRE BRANCH CIRCUIT IN THIS ROOM.

Brown AND Caldwell
BROWN AND CALDWELL
900 HAMMOND DRIVE, SUITE 500
ATLANTA, GA 30328

wendel

THIS DRAWING IS NOT VALID FOR CONSTRUCTION PURPOSES UNLESS IT BEARS THE SEAL AND SIGNATURE OF A DULY REGISTERED PROFESSIONAL

60% DESIGN DOCUMENTS

NCWSA NEWTON COUNTY WATER & SEWERAGE AUTHORITY

NCWSA OFFICE ADDITION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES AT FULL SIZE

DESIGNED: MAP
DRAWN: MAP
CHECKED: JFW
CHECKED:
APPROVED:

FILENAME

BC PROJECT NUMBER
616202
CLIENT PROJECT NUMBER

SECOND FLOOR LIGHTING PLAN - NEW WORK

DRAWING NUMBER
E102

Plot Date: 3/24/2026 8:48:06 AM Path: Autodesk Docs://NCWSA Admin Bldg_ V25/616202-NCWSA-ELEC_V25.rvt