CSC.2024.01.007

DOOR SCHEDULE

Mark	ROOM	DOOR SIZE W	H	T	TYPE	MAT.	GLZ.	FRAME TYPE	MAT.	DETAIL HEAD	JAMB	HARDWARE	NOTES
LEVEL 01													
101A	LOBBY	6'-0"	8'-0"	1"	GS	AL/GL	GL-01	SF1	AL	7 / A-802	16 / A-802	SET 1	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
101B	CORRIDOR	3'-0"	8'-0"	1"	GS	AL/GL	GL-01	SF5	AL	6 / A-802	2 / A-802	SET 2	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
102	CONFERENCE	3'-0"	8'-0"	1"	GS	AL/GL	GL-01	SF6	AL	6 / A-802	10 / A-802	SET 2	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
103	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
104	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
105	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
106	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
110	MEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 4	
111	WOMEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 4	
112	WOMEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 4	
113	MEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 4	
114	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
115	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
116	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
117	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
118	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
119	HR	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
120	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
121	BILLING	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
122	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
123	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
124	RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 5	
125	JC	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 6	
126	EXEC. OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
127	RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 5	
128	UTILITY	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 6	
129	EXEC. OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803	SET 3	
130A	CORRIDOR	3'-0"	7'-0"	1"	GS	AL/GL	GL-01		AL	7 / A-802	16 / A-802	SET 1	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.

HARDWARE SCHEDULE.

HARDWARE	Butts, 1 1/2 PR	Lockset	Privacy Set	Office Lockset	Storeroom Lockset	Passage Set	Push/Pull	Panic Hardware	Door Closer	Cylinder	Threshold	Weatherstripping	Door Stop	Drip Cap	Signage	Motor Operated	Chain Hoist	Insulated	Glass Tempered	Comments
SET 1										•									•	
SET 2							•		•				•						•	
SET 3	•			•									•							
SET 4	•		•										•		•					
SET 5	•		•										•							
SET 6	•				•				•				•							

OVERHEAD DOOR SCHEDULE

REV. #	TYPE MARK	ROOM	DOOR SIZE W	H	TYPE	MAT.	GLZ	FRAME TYPE	MAT.	HARWARE SET	NOTES
LEVEL 01											
	OVHD1	BREAK ROOM	8'-0"	8'-0"	SG	-	-	OHSV	-		OVERHEAD DOOR MANUFACTURER'S HARDWARE SET

CSC DESIGN, INC.
ARCHITECTS & ENGINEERS
135 P RICKMAN INDUSTRIAL DR.
SUITE 100 CANTON, GA 30115
Phone: (770) 345-2579

© 2025, CSC Design. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of CSC Design.

PRICING ONLY NOT FOR CONSTRUCTION

PROJECT NUMBER: 25-038

REVISIONS NO. DATE: ISSUE:

PEACH STATE CONSTRUCTION COMPANY OFFICE

265 PIPER ROAD
COVINGTON, GA 30014
NEWTON COUNTY, GEORGIA

PRICING ONLY NOT FOR CONSTRUCTION

DOOR SCHEDULE

A-801

PRICING ONLY

2/26/2026 4:10:18 PM Y:\Projects\25-038 Peach State Construction Office_Covington, GA\Arch\00 REVIT\25-038 Peach State Construction Office.rvt