DOOR SCHEDULE

Mark	ROOM	DOOR SIZE W	H	T	TYPE	MAT.	GLZ.	FRAME TYPE	FRAME MAT.	DETAIL HEAD	JAMB	SILL	HARDWARE	NOTES
LEVEL 01														
101A	LOBBY	6'-0"	8'-0"	1"	GS	AL/GL	GL-01	SF1	AL	2 / A-802	14 / A-802	12 / A-802	SET 1	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
101B	LOBBY	3'-0"	8'-0"	1"	GS	AL/GL	GL-01	SF6	AL	2 / A-802	10 / A-802		SET 2	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
102	CONFERENCE	3'-0"	8'-0"	1"	GS	AL/GL	GL-01	SF7	AL	2 / A-802	8 / A-802		SET 2	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
103	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
104	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
105	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
106	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
107A	CORRIDOR	6'-0"	7'-0"	-	-	-	-	WC	WD	3 / A-802	7 / A-802	-	-	
107B	BREAK ROOM	6'-0"	7'-0"	-	-	-	-	WC	WD	3 / A-802	7 / A-802	-	-	
108	FILE	4'-0"	7'-0"	-	-	-	-	WC	WD	3 / A-802	7 / A-802	-	-	
109	COPY	6'-0"	7'-0"	-	-	-	-	WC	WD	3 / A-802	7 / A-802	-	-	
110	MEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 4	
111	WOMEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 4	
112	WOMEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 4	
113	MEN'S RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 4	
114	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
115	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
116	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
117	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
118	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
119	HR	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
120	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
121	BILLING	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
122	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
123	OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
124	RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 5	
125	JC	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 6	
126	EXEC. OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
127	RR	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 5	
128	ELEC.	3'-0"	7'-0"	1 3/4"	F	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 6	
129	CORRIDOR	3'-0"	7'-0"	1"	GS	AL/GL	GL-01	SF4	AL	5 / A-802	14 / A-802	12 / A-802	SET 1	BALANCED OF HARDWARE BY STOREFRONT PROVIDER.
130	EXEC. OFFICE	3'-0"	7'-0"	1 3/4"	N	SCWD	N/A	HM	HM	H6 / A-803	J6 / A-803		SET 3	
131	FIRE RM	3'-0"	7'-0"	1 3/4"	F	HM	N/A	HM	HM	H1 / A-803	J4 / A-803	13 / A-802	SET 7	

HARDWARE SCHEDULE.

HARDWARE	Butts, 1 1/2 PR	Lockset	Privacy Set	Office Lockset	Storeroom Lockset	Passage Set	Push/Pull	Panic Hardware	Door Closer	Cylinder	Threshold	Weatherstripping	Door Stop	Drip Cap	Signage	Motor Operated	Chain Hoist	Insulated	Glass Tempered	Comments
SET 1										•									•	
SET 2							•		•				•						•	
SET 3	•			•									•							
SET 4	•		•										•		•					
SET 5	•		•										•							
SET 6	•				•				•											
SET 7	•				•				•		•	•						•		

OVERHEAD DOOR SCHEDULE

REV. #	TYPE MARK	ROOM	DOOR SIZE W	H	TYPE	MAT.	GLZ	FRAME TYPE	FRAME MAT.	HARWARE SET	NOTES
LEVEL 01											
	OVHD1	BREAK ROOM	8'-0"	8'-0"	SG	-	-	OHSV	-		OVERHEAD DOOR MANUFACTURER'S HARDWARE SET

CSC DESIGN, INC.
ARCHITECTS & ENGINEERS
135 P RICKMAN INDUSTRIAL DR.
SUITE 100 CANTON, GA 30115
Phone: (770) 345-2579

© 2025, CSC Design. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of CSC Design.

STATE OF GEORGIA
KEVIN B. WHIPPLE
04/28/2026
CERTIFICATE NO. RA014886
REGISTERED ARCHITECT

PROJECT NUMBER: 25-038

REVISIONS NO. DATE: ISSUE:

PEACH STATE CONSTRUCTION COMPANY OFFICE

265 PIPER ROAD
COVINGTON, GA 30014
NEWTON COUNTY, GEORGIA

DOOR SCHEDULE

A-801

ISSUED FOR CONSTRUCTION