LOUVER SCHEDULE

NOTES:

1. CONTRACTOR TO INSTALL GRAVITY DAMPER.
2. LOUVER COLOR BY ARCHITECT.
3. MANUFACTURER INSTALLED BIRD SCREEN.
4. COMBINATION LOUVER/DAMPER. ALUMINUM DRAINABLE BLADE LOUVER.

MARK	MANUFACTURER	MODEL	LOUVER SIZE			AIR FLOW (CFM)	DUITY TYPE	DAMPER TYPE	PERFORMANCE			NOTES
			WIDTH (IN)	HEIGTH (IN)	DEPTH (IN)				AIR PRESSURE DROP (IN W.G.)	FREE AREA (SF)	FREE AREA VELOCITY (FT/MIN)	
L-1	GREENHECK	ESD-403	16	16	4	315	INTAKE	GRAVITY	0.043	0.62	505	1:2:3:4
L-2	GREENHECK	ESD-403	14	16	4	250	INTAKE	GRAVITY	0.038	0.53	472	1:2:3:4
L-3	GREENHECK	ESD-403	16	12	4	190	INTAKE	GRAVITY	0.032	0.44	436	1:2:3:4

HEAT PUMP AIR HANDLING UNIT SCHEDULE

NOTES:

1. UNIT AT 208/1Ø AUXILIARY HEATER AT 208/1Ø. UNIT SHALL HAVE SINGLE POINT CONNECTION. AIR-HANDLING UNIT WITH ECM MOTOR.
2. VERIFY ELECTRIC POWER REQUIREMENTS WITH ELECTRICAL PLANS, WHICH TAKE PRECEDENCE OVER THIS INFORMATION.
3. PROVIDE AIR FILTERS, DUCT CONNECTIONS AND VIBRATION ISOLATION. PROVIDE PROGRAMMABLE THERMOSTAT AND SUPP. ELEC. HEAT MODULE CONNECTED TO UNIT FOR SINGLE POINT OF CONNECTION.
4. PROVIDE CONDENSATE TRAP(S) AS RECOMMENDED BY MANUFACTURER AND ROUTE CONDENSATE PIPING TO SUMP PIT IN BASEMENT. COORDINATE WITH PLUMBING.
5. HORIZONTAL CONFIGURATION UNIT.
6. PROVIDE AUXILIARY DRAIN PAN UNDER THE AIR HANDLERS WITH FLOAT ACTIVATED SWITCH TO SHUT THE UNIT DOWN INCASE OF CONDENSATE OVERFLOW. REFER TO DETAIL PROVIDED.
7. PROVIDE DUCT SMOKE DETECTOR IN SUPPLY AIR DUCT OF AIR-HANDLING UNIT.
8. FLOAT ACTIVATED CONDENSATE SWITCH SHALL BE PROVIDED AND INSTALLED BY HVAC CONTRACTOR. DUCT SMOKE DETECTORS SHALL BE PROVIDED BY ELECTRICAL CONTRACTOR AND INSTALLED BY HVAC CONTRACTOR.
9. PROVIDE COIL OUTLET SWITCH TO SHUT UNIT DOWN IN CASE OF CONDENSATE OVERFLOW. WIRE COIL OUTLET SWITCH IN SERIES WITH AUXILIARY CONDENSATE SWITCH LOCATED IN DRAIN PAN.
10. UNIT SHALL HAVE MANUFACTURER'S REFRIGERANT LEAK DETECTION DISSIPATION SYSTEM.
11. PROVIDE CARRIER PROGRAMMABLE THERMOSTAT WITH FOUR SMART SENSORS. LOCATE SENSORS AND THERMOSTAT AS PER DRAWINGS.
12. THERMOSTAT AND SENSORS SHALL WORK TOGETHER TO GET AN AVERAGE TEMPERATURE OF OCCUPIED SPACES.

MARK	LAUOUT BASIS		TYPE	SUPPLY FAN				EVAP. COIL ENTERING AIR DESIGN CONDITIONS		EVAP. COIL LEAVING AIR DESIGN CONDITIONS		SYSTEM COOLING MAX. REQUIREMENTS		SUPPL. HEAT (KW)	UNIT WEIGHT (LBS)	ELECTRICAL		NOTES
	MANUFACTURER	MODEL		DESIGN AIRFLOW (CFM)	OUITSIDE AIRFLOW (CFM)	ESP (IN.WG)	HP	EAT DB (°F)	EAT WB (°F)	LAT DB (°F)	LAT WB (°F)	TOTAL (MBH)	SENSIBLE (MBH)			VOLTS	PHASE	
AH-1	CARRIER	FT5ANBD60L00	HORIZONTAL	1750	315	0.50	0.75	80.0	67.0	58.8	57.9	58.44	45.90	11.3	203	208	1	1:2:3:4:5:6:7:8:9:10:11:12
AH-2	CARRIER	FT5ANBC48L00	HORIZONTAL	1400	250	0.50	0.75	78.2	65.3	56.0	54.8	44.84	33.67	7.5	168	208	1	1:2:3:4:5:6:7:8:9:10
AH-3	CARRIER	FT5ANXB24L00	HORIZONTAL	700	190	0.50	0.50	78.2	65.3	55.9	54.8	22.27	16.89	6.0	124	208	1	1:2:3:4:5:6:7:8:9:10

AIR COOLED HEAT PUMP UNIT SCHEDULE

NOTES:

1. PROVIDE WITH DEFROST CONTROLS, LOW AMBIENT HEAD PRESSURE CONTROLS, AND ANTI-SHORT CYCLE TIMER. PROVIDE COIL GUARD.
2. VERIFY ELECTRIC POWER REQUIREMENTS WITH ELECTRICAL PLANS, WHICH TAKE PRECEDENCE OVER THIS INFORMATION.
3. PROVIDE LIQUID LINE SOLENOID, CRANKCASE HEATER, TXV, START CAPACITOR AND RELAY AS RECOMMENDED BY MANUFACTURER FOR LONG LINE APPLICATIONS.
4. PROVIDE MOUNTING PAD AS PER DETAIL PROVIDED.
5. 2-STAGE COMPRESSOR UNIT.
6. PROVIDE LONG LINE ACCESSORIES PER NOTE 3 WHERE REFRIGERANT PIPE LENGTHS EXCEEDS 80-EQUIVLENT FEET.

MARK	DESCRIPTION	SYSTEM SERVES	MANUFACTURER	MODEL NO.	HEAT PUMP HEATING CAPACTY (BTU/HR)	REFRIGERANT	O.A. TEMPERATURE SUMMER (DB)	O.A. TEMPERATURE WINTER (DB)	NOMINAL CAPACITY (TONS)	SEER2	HSPF2	ELECTRICAL		NOTES
						TYPE						VOLT (V)	PH	
HP-1	CONDENSING UNIT	AH-1	CARRIER	27TPA854A003	54000	R-454B	95.0 °F	47.0 °F	5	17.5	8.1	208	1	1:2:3:4:5:6
HP-2	CONDENSING UNIT	AH-2	CARRIER	27TPA848A003	48000	R-454B	95.0 °F	47.0 °F	4	17	8.1	208	1	1:2:3:4:5:6
HP-3	CONDENSING UNIT	AH-3	CARRIER	27TPA824A003	24000	R-454B	95.0 °F	47.0 °F	2	17.5	8.1	208	1	1:2:3:4:5:6

GRILLES, REGISTERS AND DIFFUSERS SCHEDULE

NOTES:

1. PROVIDE STANDARD WHITE FINISH.
2. INSULATE BACK OF DEVICE.
3. BALANCE AIRFLOW TO QUANTITY SHOWN.
4. PROVIDE FULL SIZE SHEET METAL PLENUM ON TOP OF GRILLE FOR DUCT CONNECTION.
5. FACE SIZE IS NOMINAL 2" LARGER THAN DUCT SIZE. SEE FLOOR PLAN.
6. PROVIDE FACE OPERATED DAMPER THAT IS ACCESSIBLE FROM THE FACE OF REGISTER/DIFFUSER.

MARK	DESCRIPTION	LAYOUT BASIS		MATERIAL	FINISH	FACE SIZE	INSTALLATION TYPE	NOTES
		MANUFACTURER	MODEL					
R1	EGGCRATE GRILLE	TITUS	50F	ALUMINUM	WHITE ENAMEL	24x24	LAY-IN INSTALLATION	1:4
R2	EGGCRATE GRILLE	TITUS	50F	ALUMINUM	WHITE ENAMEL	24x12	LAY-IN INSTALLATION	1:4
S1	3-CONE DIFFUSER	TITUS	TMS	STEEL	WHITE ENAMEL	24x24	LAY-IN INSTALLATION	1:2:3
S2	3-CONE DIFFUSER	TITUS	TMS	STEEL	WHITE ENAMEL	12x12	LAY-IN INSTALLATION	1:2:3
S3	LOUVERED GRILLE	TITUS	300R	ALUMINUM	WHITE ENAMEL	NECK SIZE + 1-3/4"	SURFACE MOUNT INSTALLATION	1:3:5:6

FAN SCHEDULE

NOTES:

1. VERIFY ELECTRIC POWER REQUIREMENTS WITH ELECTRICAL PLANS, WHICH TAKE PRECEDENCE OVER THIS INFORMATION.
2. FAN TO BE INTERLOCKED WITH LIGHTS SUCH THAT FAN COMES ON WHEN LIGHTS ARE ON. PROVIDE 15-MINUTE TIME DELAY TO TURN OFF.
3. CENTRIFUGAL CEILING MOUNTED FAN. PROVIDE MANUFACTURER'S GRILLE, ROUND DUCT CONNECTION, SOLID STATE SPEED CONTROL AND MOTOR WITH THERMAL OVERLOAD.
4. FAN SHALL BE CONTROLLED BY DIGITAL TIME CLOCK 24/7-365 DAYS. TIME CLOCKS SHALL BE PROVIDED BY ELECTRICAL.

MARK	LAYOUT BASIS		FAN PROPERTIES			AIRFLOW PROPERTIES		ELECTRICAL		WEIGHT (LBS)	NOISE CRITERIA (SONES)	NOTES
	MANUFACTURER	MODEL	FAN TYPE	DRIVE TYPE	RPM	AIRFLOW (CFM)	TSP (IN.WG)	VOLTAGE (V)	PHASE			
EF-1	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	773	70	0.28	115	1	8	1.5	1:2:3
EF-2	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	685	50	0.25	115	1	8	0.8	1:3:4
EF-4	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	773	70	0.28	115	1	8	1.5	1:2:3
EF-5	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	773	70	0.28	115	1	8	1.5	1:2:3
EF-6	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	773	70	0.28	115	1	8	1.5	1:2:3
EF-7	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	773	70	0.28	115	1	8	1.5	1:2:3
EF-8	GREENHECK	SP-LP0511	CEILING EXHAUST FAN	DIRECT	773	70	0.28	115	1	8	1.5	1:2:3

MINI SPLIT & HEAT PUMP FAN COIL SYSTEM SCHEDULE SCHEDULE

NOTES:

1. ROUTE CONDENSATE AS NOTED ON DRAWINGS. COORDINATE WITH PLUMBING.
2. VERIFY ELECTRIC POWER REQUIREMENTS WITH ELECTRICAL PLANS, WHICH TAKE PRECEDENCE OVER THIS INFORMATION.
3. PROVIDE LONG LINE ACCESSORIES PER MANUFACTURER'S INSTRUCTIONS.
4. PROVIDE DISCONNECT AND ELECTRICAL CONNECTION TO OUTDOOR UNIT PER MANUFACTURER'S INSTRUCTIONS.
5. CONTRACTOR MUST COORDINATE EXACT LOCATION OF DRAIN IN THE FIELD WITH PLUMBING CONTRACTOR. MECHANICAL MUST ROUTE CONDENSATE TO APPROPRIATE LOCATION OF DISPOSAL.
6. PROVIDE RECTOR SEAL SS610E CONDENSATE OVERFLOW SWITCH TO SHUT UNIT DOWN IN CASE OF CONDENSATE OVERFLOW.
7. ABOVE CEILING CONCEALED DUCTED UNIT. PROVIDE MANUFACTURER'S INTEGRAL CONDENSATE PUMP.
8. PROVIDE MANUFACTURER'S WIRED REMOTE CONTROLLER (7 DAY PROGRAMMABLE) MODEL KSACN1401AAA.

INDOOR UNIT MARK	OUTDOOR UNIT MARK	MANUFACTURER	OUTDOOR MODEL NO.	INDOOR MODEL NO.	MIN COOLING (MBH)	MIN HEATING (MBH) @ 47F	SUPPLY AIR CFM	SEER2	HSPF2	ELECTRICAL		NOTES
										VOLTS	PHASE	
ACU-1	HPU-1	CARRIER	37MARAQ24AA3	45MBCAQ24XA3	24000	25000	635	22.1	8.1	208	1	1:2:3:4:5:6:7:8

CSC DESIGN, INC.
ARCHITECTS & ENGINEERS
135 P RICKMAN INDUSTRIAL DR.
SUITE 100 CANTON, GA 30115
Phone: (770) 345-2579

© 2026, CSC Design. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of CSC Design.

GEORGIA REGISTERED No. PE036864 PROFESSIONAL ENGINEER KRUNAL M PATEL
4/27/2026

PROJECT NUMBER: TE 25-113

REVISIONS NO. DATE: ISSUE:

PEACH STATE CONSTRUCTION COMPANY OFFICE
PIPER ROAD - NEWTON COUNTY, GEORGIA

MECHANICAL SCHEDULES

M0.6

CONSTRUCTION DOCUMENTS

TOTAL ENGINEERS
169 New Street, Macon, GA 31201
(478)741-4632 - T.E. project # 25-113
www.totalengineers.com
GA COA NO # PEF009195 EXP: 06/30/2026

4/27/2026 2:41:53 PM C:\Users\Total Engineers\Documents\M_P24_TE 25-113_jeny2PY7ZQ.rvt